



Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



# **SPECIFICATION**

## PV03501TYD54C-R

☐ Preliminary Specification
☐ Final Specification

# Kingtech Group Co.,Ltd

Made By:
Checked By:
Approved By:
Quality:
Date:
Note:

#### **CUSTOMER:**

Approved By:	
Date:	
Note:	
Tiote.	





TEL: 86-755- 23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### **Records of Revision**

DATE	REF.PAGE PARAGRAPH DRAWING No.	REVISED No.	SUMMARY	REMARK
2015-10-14		V01	First Issue	
2017-10-08		V02	Update Viewing Angle	
2017-10-17		V03	Change the drawing	





Mobile: +86-139-2528-0716





### **Contents**

1. General Specification	
2. Mechanical Drawing	
3. Block Diagram.	6
4. Interface Pin Function.	
5. Absolute Maximum Ratings	8
6. Electrical Characteristics.	9
7. Optical Characteristics	12
8. Timing Characteristics	
9. Standard Specification for Reliability	18
10. Specification of Quality Assurance	19
11. Handling Precaution	28
12 Packing Method	28








Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



# 1. General Specification

Item	Contents	Unit
LCD TYPE	TFT/TRANSMISSIVE	
MODULE SIZE (W*H*T)	76.90*63.90*4.35	MM
ACTIVE SIZE (W*H)	70.08*52.56	MM
PIXEL PITCH (W*H)	0.219*0.219	MM
NUMBER OF DOTS	320*240	
DIVER IC	HX8238D	
INTERFACE TYPE	24BIT RGB+SPI	
TOP POLARIZER TYPE	ANTI-GLARE	
RECOMMEND VIEWING DIRECTION	12	O'CLOCK
GRAY SCALE INVERSION DIRECTION	6	O'CLOCK
COLORS	16.7M	
BACKLIGHT TYPE	6-DIES WHITE LED	
TOUCH PANEL TYPE	Resistive TP	



E-mail: Helen@kingtechgroup.cn T


TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



# 2. Mechanical Drawing





E-mail: Helen@kingtechgroup.cn


TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



## 3. Block Diagram







Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### 4. Interface Pin Function

Pin No.	Symbol	Description			
1	LEDK	Cathode of LED backlight			
2	LEDK	Cathode of LED backlight			
3	LEDA	Anode of LED backlight			
4	LEDA	Anode of LED backlight			
5	YU	Touch panel control PIN: YU			
6	XR	Touch panel control PIN: XR			
7	NC	No connect			
8	RESET	RESET PIN			
9	SPENA	Chip select of serial interface			
10	SPCLK	Clock pin of serial interface			
11	SPDAT	Data input pin of serial interface			
12~19	B0~B7	Blue data bus			
20~27	G0~G7	Green data bus			
28~35	R0~R7	Red data bus			
36	HSYNC	Horizontal sync signal; negative polarity			
37	VSYNC	Vertical sync signal; negative polarity			
38	DCLK	Clock signal; latching data at the falling edge			
39	NC	Touch panel control PIN: XL			
40	NC	Touch panel control PIN: YU			
41	VCC	Power supply			
42	VCC	Power supply			
43	YD	Touch panel control PIN: YD			
44	XL	Touch panel control PIN: XL			
45	NC	No connect			
46	NC	No connect			
47	NC	No connect			
48	SEL2				
49	SEL1	Interface mode select(note)			
50	SEL0				
51	NC	No connect			
52	DEN	Display enable pin from controller			
53	GND	Power ground			
54	GND	Power ground			



E-mail: Helen@kingtechgroup.cn

TEL: 86-755- 23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



#### Note:

- 1. The mode control (SEL2) not use, it can't control CCIR601 interface, If not use CCIR601, it can floating.
- 2. For digital RGB input data format, both SYNC mode and DE+SYNC mode are supported. If DE signal is fixed low, SYNC mode is used. Otherwise, DE+SYNC mode is used. Suggest used SYNC mode!!Suggest the DE signal usually pull low.
- 3. IF select serial RGB or CCIR601/656 input mode is selected, only DX0-DX7 used, and the other short to GND, Only selected serial RGB、CCIR601/656 interface, DX BUS will enable, Digital input mode DX0 is LSB and DX7 is MSB.

#### Interface select table

SEL2	SEL1	SEL0	Interface Mode
0	0	0	Parallel-RGB Data format interface
U	U	U	(only support stripe type color filter)
0	0	1	Serial-RGB data format
0	1	0	CCIR 656 data format (640RGB)
0	1	1	CCIR 656 data format (720RGB)
1	0	0	YUV mode A data format(Cr-Y-Cb-Y)
1	0	1	YUV mode A data format(Cr-Y-Cb-Y)
1	1	0	YUV mode B data format(Cb-Y-Cr-Y)
1	1	1	YUV mode B data format(Cb-Y-Cr-Y)



E-mail: Helen@kingtechgroup.cn

TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn




### 5. Absolute Maximum Ratings

Parameter	Symbol	Min	Max	Unit
Supply voltage for analog	VDD	-0.3	4.5	V
Supply voltage for logic	VDD	-0.3	4.5	V
Supply current (One LED)	I <sub>LED</sub>		30	mA
Operating temperature	T <sub>OP</sub>	-20	+70	°C
Storage temperature	T <sub>ST</sub>	-30	+80	°C

Note: The absolute maximum rating values of this product are not allowed to be exceeded at any times. Should a module be used with any of the absolute maximum ratings exceeded, the characteristics of the module may not be recovered, or in an extreme case, the module may be permanently destroyed.





Mobile: +86-139-2528-0716





## 6. Electrical Characteristics


#### **6.1 Input Power**

Item	Symbol	Min	Тур.	Max	Unit	Applicable terminal
Supply Voltage for Analog	VDD	3.0	3.3	3.6	V	
Supply Voltage for Logic	VDD	3.0	3.3	3.6	V	
Input Voltage	$V_{\mathrm{IL}}$	GND	-	0.3VCC	V	
input voitage	$V_{ m IH}$	0.7 VCC	-	VCC	V	
Input leakage Current	$I_{LKG}$	-1		1	μΑ	

#### **6.2 Backlight Driving Conditions**

T4	Cl1	Value			TT*4	Remar
Item	Symbol	Min.	Typ.	Max.	Unit	k
Voltage for LED Backlight	VF	-	19.2	-	V	I <sub>L</sub> =40mA
Current for LED Backlight	IL		20	30	mA	
Power Consumption	P		0.384		W	
LED Life Time		30,000	50,000		Hr	Note

**Note**: Brightness to be decreased to 50% of the initial value at ambient temperature TA=25°C



TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



## 7. Touch Panel Specifications

#### 7.1 Electrical Characteristics

ITEM	SPEC	CIFICAT	`IONS	UNIT	REMARK		
	MIN.	TYP.	MAX	UNII			
Linearity	-1.5		1.5	%	After environment & life		
Linearity	-1. 5		1.0	%	test		
Terminal Resistance	400	_	900	ohm	X(Film side)		
Terminal Resistance	200	_	600	ohm	Y(Glass side)		
Insulation Resistance	20	_	_	Mohm	DC 25V 1min		
Operating Voltage	_	5	_	V	DC		

7.2 Optical Characteristics

ITEM		SPEC	CIFICAT	IONS	UNITT	DEMADIZ
		MIN.	TYP.	MAX	UNIT	REMARK
Response	e Time	_	_	10	ms	100kohm pull-up
Light Tr	ransparency	78	_	_	%	

#### 7.3 Mechanical Characteristics

100 11200110011001200100							
ITEM	SPI	ECIFICATION CONTROL OF THE CONTROL O	ONS	LINITT	REMARK		
	MIN.	TYP.	MAX	UNIT	KEWAKK		
Operation Force	_	_	100	gf	Note1		
Surface Hardness	3	_	_	Н			
Pen Sliding			100, 000	times	Note2		
Durability							
Hitting Durability	1, 000, 000			times	Note3		

Note 1: Do not operate it with a thing except a polyacetal pen (tip RO.8mm or less) or a finger, especially those with hard or sharp tips such as a ball point pen or a mechanical pencil.

Depending on the pitch & the dimension of the spacer dots in between.

Note 2: Measurement for surface area.

-Scratch 100,000 times straight line on the film with a stylus change every 20,000 times.


-Force: 100gf.
-Speed: 60mm/sec.

-Stylus: RO. 8 polyacetal tip.

Note 3: Hit 1,000,000 times on the film with an R12.5mm tip.

-Force: 250gf.

-Speed: 2 times/sec.



TEL: 86-755-23037763


Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



# 8. Optical Characteristics

LUDIA	<u></u>	CVADOI	CONDITIONS	SPEC	IFICAT	ΓΙΟΝS	IINIIT	NOTE
ITEN	VI.	SYMBOL	CONDITIONS	MIN	TYP.	MAX	UNIT  Cd/m²  ms  Degree	NOTE
Lumina	Luminance		I <sub>L</sub> =20mA	190	240	290	Cd/m <sup>2</sup>	
Contrast l	Ratio	CR	θ=0°	200	300			
Pagnanga	Timo	Ton	25℃		15	30	ma	
Response	Time	Тоғғ	23 C		35	50	IIIS	
	XR     0.581     0.601     0.621       YR     0.344     0.364     0.384							
		YR	Viewing normal	0.344	0.364	0.384		
	Color	XG		0.317	0.337	0.357		
		YG		0.571	0.591	0.611		
Coordinate		angle	0.122	0.142	0.162			
	Diue	YB		0.071	0.091	0.111	ms  Degree	
	White	Xw		0.270	0.290	0.310		
	Wille	Yw		0.294	0.314	0.334		
	Hor.	$ heta_{\scriptscriptstyle X+}$			60			
Viewing	1101.	$ heta_{\scriptscriptstyle X-}$	CR≥10		60			
Angle	Ver.	$ heta_{\scriptscriptstyle Y+}$	CK=10		50		Degree	
	V C1.	$ heta_{\scriptscriptstyle Y-}$			60			
Uniformity	Un			80			%	




TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn




### Note 1: Definition of Viewing Angle θx and θy:



#### Note 2: Definition of contrast ratio CR:

 $CR = \frac{Luminance of white state}{Luminance of black state}$ 

**Note 3: Definition of Response Time (Tr,Tf)** 



TEL: 86-755-23037763

Mobile: +86-139-2528-0716


Web: www.kingtechgroup.cn



#### **Note 4: Definition of Luminance**


#### **1** The Brightness Test Equipment Setup


Field=2° (As measuring "black" image, field=2° is the best testing condition)



The center of the screen

### **2** The Brightness Test Point Setup








Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn




# 9. Timing Characteristics

### 9.1 Pixel Timing Diagram



Characteristics	Symbol	Mi	n.	Ту	p.	Ma	ix.	Unit
Characteristics	Symbol	24 bit	8 bit	24 bit	8 bit	24 bit	8 bit	Onit
DOTCLK Frequency	fDOTCLK	-	-	6.5	19.5	10	30	MHz
DOTCLK Period	tDOTCLK	100	33.3	154	51.3	~	- 2	ns
Vertical Sync Setup Time	tvsys	20	10		2	1 <u>2</u> 00	2	ns
Vertical Sync Hold Time	tvsyh	20	10	-		S=3	-	ns
Horizontal Sync Setup Time	thsys	20	10	-	-	940	-	ns
Horizontal Sync Hold Time	thsyh	20	10	25	548	1 120		ns
Phase difference of Sync Signal Falling Edge	thv	1		45	5	24	10	tDOTCLK
DOTCLK Low Period	tCKL	50	15	-	( <del>-</del>	-		ns
DOTCLK High Period	tCKH	50	15			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- 2	ns
Data Setup Time	tds	12	10	50		820	2	ns
Data hold Time	tdh	12	10	- 5	853	150		ns
Reset pulse width	tRES	1	0					μS

Note: External clock source must be provided to DOTCLK pin of HX8238-D. The driver will not operate if absent of the clocking signal.




TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### 9.2 SYNC mode Timing Diagram



Characterie	Characteristics		Mi	n.	Ty	p.	Ma	ax.	Unit
Characteristics		Symbol	24 bit	8 bit	24 bit	8 bit	24 bit	8 bit	Ullit
DOTCLK Frequen	cy_	fDOTCLK	(5)		6.5	19.5	10	30	MHz
DOTCLK Period		tDOTCLK )	100	33.3	154	51.3		329	ns
Horizontal Freque	ncy (Line)	/\fh\	-	3	14	.9	22	.35	KHz
Vertical Frequency	(Refresh)	< fV)	( <del>)</del>	8	6	0	9	0	Hz
Horizontal Back P	orch	tHBP	-	22	68	204		80.75	tDOTCLK
Horizontal Front P	orch	tHFP	1371	-	20	60			tDOTCLK
Horizontal Data St	art Point	tHBP	100	. 3	68	204	(2)	327	tDOTCLK
Horizontal Blankin	g Period	tHBP + tHFP	-	- 29	88	264	198	140	tDOTCLK
Horizontal Display	Area	HDISP	1(4)	- 23	320	960	-	5941	tDOTCLK
Horizontal Cycle	i i	Hcycle			408	1224	450	1350	tDOTCLK
Vertical Back Pord	h	tVBP	-		18		1-		Lines
Vertical Front Por	ch	tVFP	32	Š.	4		327		Lines
Vertical Data Star	t Point	tVBP	372	8	18			- P	Lines
Vertical Blanking I	Period	tVBP + tVFP	( <del>)</del>	8(	2	2	546		Lines
Madical Disales	NTSC	03			24	10			
Vertical Display Area	PAL	VDISP	27 <del>.</del>	8	280(PALM=0)		7	7.0	Lines
Alea .	PAL	0	905.45		288(PALM=1)				
Vertical Ovela	NTSC	Veuele	32	8	26	52	21	-0	Lines
Vertical Cycle	PAL	Vcycle	661		313		350		Lines




TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn




### 9.3 DE mode Timing Diagram



Characteristics	Symbol	Min.		Тур.		Ma	ax.	Unit
Characteristics	Symbol	24-bit	8-bit	24- bit	8-bit	24-bit	8-bit	Onit
DOTCLK Frequency	fDOTCLK	- ,	3/1	6.5	19.5	10	30	MHz
DOTCLK Period	tDOTCLK	100	33.3	154	51.3		-	ns
Horizontal Blanking Period	tHBP + tHFP	52	146	88	264	180	960	tDOTCLK
Horizontal Display Area	HDISP	in the	S -	320	960	- 2	120	tDOTCLK
Horizontal Cycle	Hcycle	372	1106	408	1224	500	1920	tDOTCLK
Vertical Blanking Period	tVBP + tVFP	V 2	2	) <u>-</u>		4	7	Lines
Vertical Display Area	VDISP	5	1	24	0	195	-	Lines
Vertical Cycle	Vcycle	24	12	) (A		28	87	Lines

Note: The above parallel RGB interface timing sequence is for reference only. For the other interface timing sequence, please refer to the driver IC(HX8238D) data sheet.





Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn




## 10. Standard Specification for Reliability

### 10.1 Standard Specification for Reliability of LCD Module

No.	Item	Description
01	High temperature operation	The sample should be allowed to stand at 70°C for 120 hours under driving condition and then returning it to normal temperature condition, and allowing it stand for 2 hours.
02	Low temperature operation	The sample should be allowed to stand at -20°C for 120 hours under driving condition and then returning it to normal temperature condition, and allowing it stand for 2 hours.
03	High temperature storage	The sample should be allowed to stand at 80°C for 240 hours under no-load condition, and then returning it to normal temperature condition and allowing it stand for 2 hours.
04	Low temperature storage	The sample should be allowed to stand at -30°C for 240 hours under no-load condition, then returning it to normal temperature condition, and allowing it stand for 2 hours.
05	Moisture storage	The sample should be allowed to stand at 60°C, 90%RH MAX for 240 hours under no-load condition, then taking it out and drying it at normal temperature for 2 hours.
06	Thermal shock storage	The sample should be allowed to stand the following 10 cycles: -30°C for 30 minutes → normal temperature for 5 minutes → +80°C for 30 minutes → normal temperature for 5 minutes, as one cycle.
07	Packing vibration	Frequency range: 10Hz ~ 55Hz Amplitude of vibration: 1.5mm Sweep time: 12 min X, Y, Z 2 hours for each direction.
08	Packing drop test	According to ASTM-D-5327.
00	Electrical	Air: $\pm 4KV 150 pF/330\Omega 5$ times
09	Static Discharge	Contact: $\pm 2KV 150pF/330\Omega 5$ time

<sup>\*</sup>Sample size for each test item is 3~5pcs





Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### 10.2 Testing Conditions and Inspection Criteria

For the final test, the testing sample must be stored at room temperature for 24 hours. After the tests listed in Table 9.2, standard specifications for reliability will be executed in order to ensure stability.

No.	Item	Test Model	In section Criteria
01	Current Consumption	Refer To Specification	The current consumption should conform to the product specification.
02	Contrast	Refer To Specification	After the tests have been executed, the contrast must be larger than half of its initial value prior to the tests.
03	Appearance	Visual inspection	Defect free.

#### **10.3 MTBF**



E-mail: Helen@kingtechgroup.cn

TEL: 86-755- 23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### 11. Specification of Quality Assurance

This standard of Quality Assurance confirms to the quality of LCD module products supplied by Kingtech

### 11.1 Quality Test

Before delivering, the supplier should conduct the following tests to confirm the quality of products.

- Electrical-Optical Characteristics: According to the individual specification to test the product.
- Appearance Characteristics: According to the individual specification to test the product.
- Reliability Characteristics: According to the definition of reliability on the specification for testing products.

### 11.2 Delivery Test

Before delivering, the supplier should conduct the delivery test.

- Test method: According to MIL-STD105E.General Inspection Level II take a single time.
- The defects classify of AQL as following:

Major defect: AQL = 0.65 Minor defect: AQL = 2.5 Total defects: AQL = 2.5

### 11.3 Non-conforming Analysis & Deal with Manners

#### 11.3.1 Non-conforming Analysis

- Purchaser should provide the data detail of non-conforming sample and the non-conforming.
- After receiving the data detail from purchaser, the analysis of non-conforming should be finished within two weeks.
- If the analysis can't be finished on time, supplier must notice purchaser 3 days in advance.

#### 11.3.2 Disposition of non-conforming

- If any product defect be found during assembling, supplier must change the good for every defect after confirmation.
- Both supplier and customer should analyze the reason and discuss the disposition of non-conforming when the reason of nonconforming is not sure.

# Kingtech Group Co., Ltd. ---- Lcd Touchscreen Expert

Add: 2nd Floor, Building C, Jia Huang Yuan Technical Park, Tiegang, Xixiang, Bao'an District, Shenzhen city, Guangdong province, P.R.China 518126

E-mail: Helen@kingtechgroup.cn

TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### 11.4 Agreement items


Both parties should negotiate together when the following problems happen.

- There is any problem of standard of quality assurance, and both sides should agree that it must be modified.
- There is any argument item which does not record in the standard of quality assurance.
- Any other special problem.


### 11.5 Standard of the Product Appearance Test

#### 11.5.1 Manner of appearance test

- The test must be under 20W × 2 or 40W fluorescent light, and the distance of view must be at 30±5cm.
- When test the model of transmissive product must add the reflective plate.
- The test direction is base on around 10° of vertical line.
- Temperature: 25±5 °C Humidity: 60±10%RH



• Definition of area:



A: Viewing area B: Outside viewing area



E-mail: Helen@kingtechgroup.cn TEL: 86-755- 23037763


Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



#### 11.5.2 Basic principle

- When the standard cannot be described, AQL will be applied.
- The sample of the lowest acceptable quality level must be negotiated by both supplier and customer when any dispute happened.
- New item must be added on time when it is necessary.



TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



## 11.6 Inspection Specification

NO.	Item		Cri	terion		AQL		
01	Electrical Testing	<ul> <li>1.1 Missing vertical, horizontal segment, segment contrast defect.</li> <li>1.2 Missing character, dot or icon.</li> <li>1.3 Display malfunction.</li> <li>1.4 No function or no display.</li> <li>1.5 Current consumption exceeds product specifications.</li> <li>1.6 LCD viewing angle defect.</li> <li>1.7 Mixed product types.</li> <li>1.8 Flicker</li> </ul>						
02	Black or White spots or Bright spots or Color spots on LCD (Display only)	2.1 White and black or of Five spots. 2.2 Densely spaced: No	-			2.5		
	LCD and Touch Panel black spots, white	3.1 Round type: As follows: $\Phi = (X+Y)/2$ * Densely spaced: No		Size(mm) $\Phi \le 0.10$ $0.10 < \Phi \le 0.20$ $0.20 < \Phi \le 0.25$ $0.25 < \Phi \le 0.30$ $0.30 < \Phi$	Acceptable Q'ty Accept no dense  2  2  1  0  o spots within 3mm.	2.5		
03	spots, white spots, contaminati on (non – display)	3.2 Line type: (As follows)  W  L	Length( mm)  L≤3.0 L≤2.5	Width(mm) $W \le 0.02$ $0.02 < W \le 0.05$ $0.03 < W \le 0.08$ $0.08 < W$	Acceptable Q'ty  Accept no dense  2  Rejection  vo lines within 3mm.	2.5		

# KINGTECH Kingtech Group Co., Ltd. --- Lcd Touchscreen Expert

Add: 2nd Floor, Building C, Jia Huang Yuan Technical Park, Tiegang, Xixiang, Bao'an District, Shenzhen city, Guangdong province, P.R.China 518126.

E-mail: Helen@kingtechgroup.cn

TEL: 86-755-23037763

Mobile: +86-139-2528-0716



NO.	Item	Crit	erion		AQL
04	Polarizer bubbles	If bubbles are visible, judge using black spot specifications, not easy to find, must check in specify direction	Size Φ(mm) $\Phi \le 0.20$ $0.20 < \Phi \le 0.50$ $0.50 < \Phi \le 1.00$ $1.00 < \Phi$	Acceptable Q'ty Accept no dense 3 2 0	2.5
05	Scratches	Follow NO.3 -2 Line Type.	Total Q'ty	3	
06	Chipped glass	Symbols: x: Chip length y: Chip width k: Seal width t: Glass thickness L: Electrode pad length 6.1 General glass chip: 6.1.1 Chip on panel surface and cr  z: Chip thickness y: Chip widt  Z ≤ 1/2t Not over y area  1/2t< z ≤ 2t Not excee  Unit: mm  If there are 2 or more chips, x i 6.1.2 Corner crack:  z: Chip thickness y: Chip widt  Z ≤ 1/2t Not over y area  1/2t< z ≤ 2t Not excee  Unit: mm  If there are 2 or more chips, x i  Symbols:  Z ≤ 1/2t Not over y area  1/2t< z ≤ 2t Not excee  Unit: mm  If there are 2 or more chips, x i  If there are 2 or more chips, x i	th x: Chip viewing $x \le a$ and $a$ the total length of $a$ the total length of $a$ and $a$ a	length 1/8a 1/8a each chip  length 1/8a 1/8a  1/8a	2.5



E-mail: Helen@kingtechgroup.cn

TEL: 86-755-23037763

Mobile: +86-139-2528-0716



NO.	Item	Criterion	AQL
08	Cracked glass	The LCD with extensive crack is not acceptable.	2.5
09	Backlight elements	<ul> <li>9.1 Illumination source flickers when lit.</li> <li>9.2 Spots or scratches that appear when lit must be judged. Using LCD spot, lines and contamination standards.</li> <li>9.3 Backlight doesn't light or color is wrong.</li> </ul>	2.5 2.5 0.65
10	Bezel	Bezel must comply with product specifications.	2.5
11	PCB、COB	<ul> <li>11.1 COB seal may not have pinholes larger than 0.2mm or contamination.</li> <li>11.2 COB seal surface may not have pinholes through to the IC.</li> <li>11.3 The height of the COB should not exceed the height indicated in the assembly diagram.</li> <li>11.4 There may not be more than 2mm of sealant outside the seal area on PCB. And there should be no more than three places.</li> <li>11.5 Parts on PCB must be the same as on the production characteristic chart, There should be no wrong parts, missing parts or excess parts.</li> <li>11.6 The jumper on the PCB should conform to the product characteristic chart.</li> </ul>	2.5 2.5 2.5 2.5 0.65
12	FPC	12.1 FPC terminal damage ≤ 1/2 FPC terminal width and can not affect the function, we judge accept. 12.2 FPC alignment hole damage ≤ 1/2 alignment area and can not affect the function, we judge accept.	2.5 2.5
13	Soldering	<ul><li>13.1 No cold solder joints, missing solder connections, oxidation or icicle.</li><li>13.2 No short circuits in components on PCB or FPC.</li></ul>	2.5 0.65

# Kingtech Group Co., Ltd. --- Lcd Touchscreen Expert

Add: 2nd Floor, Building C, Jia Huang Yuan Technical Park, Tiegang, Xixiang, Bao'an District, Shenzhen city, Guangdong province, P.R.China 518126.

E-mail: Helen@kingtechgroup.cn

TEL: 86-755- 23037763

Mobile: +86-139-2528-0716



NO.	Item	Criterion			
		Symbols: x: Chip length y: Chip width z: Chip thickness k: Seal width t: Glass thickness a: LCD side length L: Electrode pad length 7.2 Protrusion over terminal: 7.2.1 Chip on electrode pad:			
		y: Chip width   x: Chip length   z: Chip thickness			
		$y \le 0.5 \text{mm}$ $x \le 1/8 a$ $0 < z \le t$			
07	Glass crack	7.2.2 Non-conductive portion:			
		y: Chip width   x: Chip length   z: Chip thickness			
		$y \le L \qquad \qquad x \le 1/8a \qquad \qquad 0 < z \le t$			
		<ul> <li>If there chipped area touches the ITO terminal, over 2/3 of the ITO must remain and be inspected according to electrode terminal specifications.</li> <li>If the product will be heat sealed by the customer, the alignment mark must not be damaged.</li> <li>7.2.3 Substrate protuberance and internal crack</li> </ul> y: width x: length y ≤ 1/3L X ≤ a			



E-mail: Helen@kingtechgroup.cn

TEL: 86-755-23037763

Mobile: +86-139-2528-0716



NO.	Item	Criterion			AQL
14	Touch Panel Chipped glass	k: Seal width t: 'L: Electrode pad length 14.1 General glass class clas	hip: I surface and crack between the surface and crack between th	x: Chip length  x ≤ 1/8a	
		z: Chip thickness	y: Chip width	x: Chip length	
		z≦t	≤ 1/2 k and not over viewing area	x ≤ 1/8a	
		<ul><li>⊙ Unit: mm</li><li>⊙ If there are 2 or m</li></ul>	nore chips, x is the total	length of each chip	







Mobile: +86-139-2528-0716



NO.	Item	Criterion		
15	Touch Panel(Fish eye dent and bubble on film)	$\begin{array}{ c c c }\hline SIZE(mm) & Acceptable Q'ty\\ \hline \Phi \leq 0.2 & Accept no dense\\ \hline 0.2 < D \leq 0.4 & 5\\ \hline 0.4 < D \leq 0.5 & 2\\ \hline 0.5 < D & 0\\ \hline \end{array}$	2.5	
16	Touch Panel Newton ring	Newton ring dimension $\leq 1/2$ touch panel area and not affect font and line distortion ( $\leq 2.5\%$ ), it is acceptable.		
17	Touch Panel Linearity	Less than 2.5% is acceptable.		
18	LCD Ripple	Touch the touch panel, cannot see the LCD ripple. Pen: R 1.0mm silicon rubber. Operation Force: 80g		
19	General appearance	<ul> <li>19.1 Pin type must match type in specification sheet.</li> <li>19.2 LCD pin loose or missing pins.</li> <li>19.3 Product packaging must the same as specified on packaging specification sheet.</li> <li>19.4 Product dimension and structure must conform to product specification sheet.</li> </ul>	0.65 0.65 0.65 0.65	



TEL: 86-755-23037763

Mobile: +86-139-2528-0716

Web: www.kingtechgroup.cn



### 12. Handling Precaution

#### 12.1 Handling of LCM

- Avoid external shock.
- Don't apply excessive force on the surface.
- Liquid in LCD is hazardous substance, do not lick or swallow. When the liquid is attaching to your hand, skin, cloth, etc., wash it thoroughly and immediately.
- Don't operate it above the absolute maximum rating.
- Don't disassemble the LCM.
- The operators should wear protections whenever he/she comes into contact with the module. Never touch any of the conductive parts such as the LSI pads, the copper leads on the PCB and the interface terminals with any parts of the human body.
- The modules should be kept in antistatic bags or other containers resistant to static for storage.
- The module is coated with a film to protect the display surface, be careful when peeling off this protective film since static electricity may be generated.

### 12.2 Storage

- Store it in an ambient temperature of 25±10°C, and in a relative humidity of 50±10%RH. Don't expose to sunlight or fluorescent light.
- Store it in a clean environment, free from dust, active gas, and solvent.
- Store it in anti-static electricity container.
- Store it without any physical load.

### 12.3 Soldering

- Use only soldering irons with proper grounding and no leakage.
- Iron: no higher than 280±10°C and less than 3 sec during hand soldering.
- Rewiring: no more than 2 times.

## 13. Packing Method

----TBD